



BLIJLEVEN Demolition

Bommelweg 42-44
4014 PW Wadenoijen
info@blijleven.info
www.blijleven.info

Tel.: +31 (0)345 569 602
Fax: +31 (0)345 569 802

Unique in the Netherlands!
Visit our website



Removal of noise barrier at A12 Arnhem



Bush hammering



Demolition of business premises



Bush hammering



Gluing of cuttings



Pneumatic drilling of holes



Cutting



Pneumatic drilling

- demolition works • pile breaking • pilehead cutting • diamond drill bits • diamond saws

View a project

Type of project

Producer

Size

Configuration

Show projects

Drilling with a Ø 350 diamond drill bit,
1,500 mm long



Demolition of back area



Coentunnel, cracking of 2,000 piles





Pilehead

Breda - The bulk of work is currently done by workers from Blijleven Sloopwerken, where they have been busy for the past few weeks with manual cutting of 295 Olivier piles on the Dr Struycken square. A length of 2 to 2.5 metres must be removed from the foundation piles that vary in length from 12.5 up to 17 metres. The piles, made by Verhoef Funderingstechnieken, are

being lengthened to ensure that the end results required from the piles can be guaranteed.

Because the piles stand close to each other a hydraulic cracker cannot be used. „There’s a lot of work, but it is going quite fast,” said Ludo Peeters, project leader at the internal services of the Dutch Construction Union (NBU). He expects that all of the piles

will be at the correct length within one week. The construction company has built three buildings on the square with 211 apartments available for sale or for rent, including a residential tower of 48 meters high. Shops, offices and social facilities are available on the ground floor.

Photo: Boyd Smith; text: Yvonne Ton